PUBLIC AND PRIVATE IMPROVEMENTS CODE

OF THE TOWNSHIP OF UPPER ST. CLAIR

TABLE OF CONTENTS

99.1. ADMINISTRATION AND GENERAL REGULATIONS....2

99.1.1. Title....2

99.1.2. General Purposes....2

99.1.3. Interpretation of the Provisions of the CODE....2

99.1.4. Applicability....2

99.1.5. Requirements for CONTRACTS....2

99.1.6. Basis of Payment....3

99.1.7. Construction of PUBLIC and PRIVATE IMPROVEMENTS....3

99.1.8. Control of Construction PUBLIC and PRIVATE IMPROVEMENTS by DEVELOPERS....3

99.1.7.1. Notice prior to start of work....3

99.1.7.2. Supervision and Superintendence....4

99.1.7.3. Site Appearance....4

99.1.7.4. Dirt Control; Parking....4

99.1.7.5. Hours of Construction....4

99.1.9. Control of Construction of UTILITIES by PUBLIC UTILITY COMPANIES....5

99.1.10. Violations and Penalties....5

99.1.11. Stop Work Order....5

99.1.11.1. Notice to stop work....5

99.1.11.2. Unlawful continuance....5

99.1.12. Procedure for Acceptance of PUBLIC IMPROVEMENTS....6

99.1.13. Procedure for Approval of PRIVATE IMPROVEMENTS 6

99.1.13.1. Notification by DEVELOPER, Submittal of AS-BUILT PLANS 6

99.1.13.2. TOWNSHIP Authorization for Inspection 7

99.1.13.3. Inspection and Report.....7

99.1.13.4. Payment of Inspection Fees.....7

99.1.13.4.1. TOWNSHIP Notification to DEVELOPER 7

99.1.13.4.2. Failure of TOWNSHIP to act 7

99.1.13.4.3. Completion of Rejected PRIVATE IMPROVEMENTS.....7

99.1.14. Fees for PUBLIC and PRIVATE IMPROVEMENTS.....8

99.1.15. Basis of Payment……8

99.1.16. Enactment of Amendments to the CODE 8

99.2. DEFINITIONS.....11

99.2.1. AS-BUILT PLAN 12

99.2.2. CARTWAY 12

99.2.3. CODE.....12

99.2.4. CONSTRUCTION STANDARDS.....12

99.2.5. CONTRACT 12

99.2.6. DEVELOPER.....12

99.2.7. DRIVEWAY 12

99.2.8. DWELLING, SINGLE-FAMILY 12

99.2.9. EASEMENT, DRAINAGE……..……12

99.2.10. EASEMENT……...……12

99.2.11. ENGINEER 12

99.2.12. FINANCIAL SECURITY 13
99.2.13. LANDOWNERS 13
99.2.14. PARKING AREA 13
99.2.15. PRIVATE IMPROVEMENTS 13
99.2.16. PUBLIC IMPROVEMENTS 13
99.2.17. PUBLIC UTILITY COMPANY 13
99.2.18. RIGHT-OF-WAY, PRIVATE 13
99.2.19. RIGHT-OF-WAY, PUBLIC 13
99.2.20. SEWERS, SANITARY 13
99.2.21. SEWERS, STORM 13
99.2.22. SIDEWALK 13
99.2.23. SPECIFICATIONS 14
99.2.24. STREET 14
99.2.25. TOWNSHIP 14
99.2.26. TOWNSHIP MANAGER 14
99.2.27. UTILITY 14
99.2.28. WALKWAY 14
99.3. GENERAL SPECIFICATIONS 17
99.3.1. PROJECT ADMINISTRATION REQUIREMENTS 18
99.3.1.1. COOPERATION AND COORDINATION OF WORK 18
99.3.1.2. SCHEDULE OF OPERATIONS 18
99.3.1.3. JOB CONFERENCES 19
99.3.1.4. PROJECT RECORDS 19

99.3.1.5. CONSTRUCTION PHOTOGRAPHS 19

99.3.2. SITE PREPARATION 19

99.3.2.1. DESCRIPTION 19

99.3.2.1.1. SCOPE 19

99.3.2.2. CONSTRUCTION DETAILS 20

99.3.2.2.1. GENERAL 20

99.3.2.2.2. CLEARING AND GRUBBING 21

99.3.2.2.3. REMOVAL OF STRUCTURES, UTILITIES AND OBSTRUCTIONS 21

99.3.2.2.4. PROTECTION OF EXISTING STRUCTURES AND UTILITIES 24

99.3.2.2.5. PROTECTION OF EXISTING LANDSCAPING AND NATURAL FEATURES 24

99.3.2.2.6. MAINTENANCE AND PROTECTION OF TRAFFIC 25

99.3.2.2.7. MUD CONTROL 26

99.3.2.2.8. CONSTRUCTION AND MAINTENANCE OF ACCESS ROADS, CONSTRUCTION ROADS AND STAGING AREAS 26

99.3.2.2.9. GENERAL REQUIREMENTS 26

99.3.3. SOIL EROSION AND WATER POLLUTION CONTROL 27

99.3.3.1. DESCRIPTION 27

99.3.3.1.1. SCOPE 27

99.3.3.1.2. COORDINATION WITH PERMANENT CONTROL FEATURES 27

99.3.3.1.3. COMPLIANCE WITH REGULATIONS 27

99.3.3.2. CONSTRUCTION DETAILS 28

99.3.3.2.1. SCHEDULE OF WORK 28

99.3.3.2.2. SEDIMENT AND POLLUTANTS 29
99.3.3.2.3. AREA OF WORK.....30
99.3.3.2.4. SPECIFIC REQUIREMENTS 30
99.3.3.3. MATERIALS 31
99.3.3.3.1. GEOTEXTILES 31
99.3.3.3.2. DRY RIP-RAP 31
99.3.3.3.3. GROUTED RIP-RAP.....31
99.3.3.3.4. BASIS OF PAYMENT 32
99.3.4. EXCAVATION AND EMBANKMENT 32
99.3.4.1. DESCRIPTION.....32
99.3.4.1.1. SCOPE.....32
99.3.4.1.2. WORK SPECIFIED UNDER OTHER SECTIONS.....33
99.3.4.1.3. TOPOGRAPHIC INFORMATION 33
99.3.4.1.4. SUBSURFACE INFORMATION 34
99.3.4.1.5. QUALITY CONTROL 35
99.3.4.2. CONSTRUCTION DETAILS 35
99.3.4.2.1. GENERAL 35
99.3.4.2.2. DETENTION POND MAINTENANCE AND MODIFICATIONS.....36
99.3.4.2.3. DRAINAGE DURING CONSTRUCTION.....37
99.3.4.2.4. DRAINAGE INTERCEPTOR DITCHES 37
99.3.4.2.5. CHANNEL CONSTRUCTION.....38
99.3.4.2.6. STORM SEWER INSTALLATIONS 38
99.3.4.2.7. DUST CONTROL.....39

99.3.4.2.8. EXCAVATION....40
99.3.4.2.9. DISPOSAL OF MATERIAL OUTSIDE THE WORK SITE....41
99.3.4.2.10. TOPSOIL....42
99.3.4.2.11. ROCK EXCAVATION....43
99.3.4.2.12. SUBGRADE UNDERCUTTING....45
99.3.4.2.13. EMBANKMENT....45
99.3.4.2.14. PROOF ROLLING OF SUBGRADE SURFACE....48
99.3.4.2.15. PAVEMENT AND BUILDING SUBGRADE....48
99.3.4.2.16. COORDINATION OF OPERATIONS....49
99.3.4.3. TEMPORARY FACILITIES....49
99.3.4.3.1. SCOPE AND REQUIREMENTS....49
99.3.5. TRENCH EXCAVATION AND BACKFILL....50
99.3.5.1. DESCRIPTION....50
99.3.5.1.1. SCOPE....50
99.3.5.1.2. WORK SPECIFIED UNDER OTHER SECTIONS....50
99.3.5.1.3. EXISTING UTILITIES AND SUBSURFACE STRUCTURES....51
99.3.5.2. CONSTRUCTION DETAILS....51
99.3.5.2.1. GENERAL....51
99.3.5.2.2. TRENCH EXCAVATION....52
99.3.5.2.3. ROCK EXCAVATION IN TRENCH & PAYMENT....54
99.3.5.2.4. ADDITIONAL TRENCH EXCAVATION....56
99.3.5.2.5. TUNNELING AND JACKING OF PIPE....57
99.3.5.2.6. PIPE BEDDING....57

99.3.5.2.7. IMPERFECT TRENCH 58
99.3.5.2.8. BACKFILLING 58
99.3.5.2.9. SHEETING, SHORING AND BRACING 61
99. 3.5.2.10. DISPOSAL OF WATER 61
99.3.5.2.11. RESTORATION 62
99.3.6. STORM DRAINAGE 65
99.3.6.1. DESCRIPTION 65
99.3.6.1.1. SCOPE 65
99.3.6.1.2. WORK SPECIFIED UNDER OTHER SECTIONS 66
99.3.6.2. CONSTRUCTION DETAILS 66
99.3.6.2.1 GENERAL 66
99.3.6.2.2. STORAGE AND HANDLING OF PIPE 66
99.3.6.2.3. DAMAGE TO PIPE 66
99.3.6.2.4. PIPE INSTALLATION 67
99.3.6.2.5. PIPE JOINTS 69
99.3.6.2.6. END SECTIONS 69
99.3.6.2.7. MANHOLES, CATCH BASINS, AND INLETS 70
99.3.6.2.8. CONNECTIONS TO EXISTING FACILITIES 72
99.3.6.2.9. RECONSTRUCTION OF EXISTING STRUCTURES 73
99.3.6.2.10. RELOCATION AND/OR ABANDONMENT OF EXISTING FACILITIES 74
99.3.6.2.11. LEADER DRAINS 74
99.3.6.2.12. UNDERDRAINS 75
99.3.6.2.13. LEAKAGE TESTS 75

99.3.6.2.14 CLEANING AND REPAIR 77
99.3.6.2.15. FINAL INSPECTION 77
99.3.6.3. MATERIALS 78
99.3.6.3.1. STORM DRAIN PIPE, FITTINGS AND JOINTS 78
99.3.6.3.2. UNDERDRAIN PIPE AND FILTER MATERIAL 81
99.3.6.3.3. STRUCTURES 81
99.3.7. SANITARY SEWERS 84
99.3.7.1. DESCRIPTION 84
99.3.7.1.1. SCOPE 84
99.3.7.1.2. WORK SPECIFIED UNDER OTHER ARTICLES 84
99.3.7.2. CONSTRUCTION DETAILS 85
99.3.7.2.1. GENERAL 85
99.3.7.2.2. STORAGE AND HANDLING OF PIPE 85
99.3.7.2.3. DAMAGE TO PIPE 85
99.3.7.2.4. PIPE INSTALLATION 85
99.3.7.2.5. PIPE JOINTS 87
99.3.7.2.6. MANHOLES 87
99.3.7.2.7. CONNECTIONS TO EXISTING FACILITIES 90
99.3.7.2.8. ALTERATION AND/OR RECONSTRUCTION OF EXISTING STRUCTURES 90
99.3.7.2.9. RELOCATION AND/OR ABANDONMENT OF EXISTING FACILITIES 91
99.3.7.2.10. SERVICE LINES 91

99.3.7.2.11. TESTS 91
99.3.7.2.12. CLEANING AND REPAIR....94
99.3.7.2.13. FINAL INSPECTION....94
99.3.7.3. MATERIALS 95
99.3.7.3.1. SANITARY SEWER PIPE, FITTINGS AND JOINTS....95
99.3.7.3.2. MANHOLES 97
99.3.8. CEMENT CONCRETE 100
99.3.8.1. DESCRIPTION....100
99.3.8.1.1 CLASSES OF CONCRETE 100
99.3.8.2 MATERIAL TESTS....100
99.3.8.3. METHOD OF CONSTRUCTION....100
99.3.8.3.1. GENERAL....100
99.3.8.3.2. CURING 101
99.3.8.3.3. FINISHING....101
99.3.8.3.4. PROTECTIVE COATING FOR CONCRETE 101
99.3.9. CURBS AND SIDEWALKS 102
99.3.9.1. DESCRIPTION....102
99.3.9.1.1. SCOPE....102
99.3.9.2. CONSTRUCTION DETAILS 102
99.3.9.2.1. GENERAL....102
99.3.9.2.2. CURBS 102
99.3.9.2.3. SIDEWALKS 107

99.3.9.2.4. BACKFILLING BEHIND CURBS AND SIDEWALKS 109
99.3.10. PAVEMENTS 109
99.3.10.1. DESCRIPTION 109
99.3.10.1.1. SCOPE 109
99.3.10.1.2. PAVEMENTS WITHIN PUBLIC HIGHWAYS 110
99.3.10.1.3. WORK SPECIFIED UNDER OTHER SECTION 110
99.3.10.2. CONSTRUCTION DETAILS 110
99.3.10.2.1. GENERAL 110
99.3.10.2.2. PREPARATION OF SUBGRADE 111
99.3.10.2.3. PREPARATION FOR PAVEMENT INSTALLATION 112
99.3.10.2.4. AGGREGATE BASE COURSE 114
99.3.10.2.5. BITUMINOUS CONCRETE PAVEMENTS 118
99.3.10.2.6. BITUMINOUS CONCRETE OVERLAYS 119
99.3.10.2.7. TEMPORARY PAVEMENT 120
99.3.10.2.8. PERMANENT PAVEMENT REPLACEMENT 121
99.3.10.2.9. SEAL COAT 122
99.3.10.2.10. SLURRY SEAL TREATMENT 122
99.3.10.2.11. MATERIALS TESTS 122
99.3.10.2.12. CONCRETE PAVEMENT 122
99.3.10.2.13. BERM RESTORATION AND BACKFILL 123
99.3.10.2.14. SELECTED MATERIAL PAVEMENTS 123
99.3.10.3. GUARANTEE AND MAINTENANCE 123
99.3.11. TRAFFIC CONTROL DEVICES 123

99.3.11.1. DESCRIPTION 123
99.3.11.1.1. SCOPE 124
99.3.11.2. LINE STRIPPING AND PAVEMENT MARKINGS 124
99.3.11.2.1. GENERAL 124
99.3.11.2.2. APPLICATION OF PAVEMENT MARKINGS 125
99.3.11.2.3. STRIPING SCHEDULE 125
99.3.11.2.4. MATERIALS 126
99.3.11.2.5. PAVEMENT MARKING REMOVAL 126
99.3.11.3. REFLECTORIZED SIGNS 126
99.3.11.3.1. GENERAL 126
99.3.11.3.2. MATERIALS 127
99.3.11.4. NON-REFLECTORIZED SIGNS 127
99.3.11.4.1. GENERAL 127
99.3.11.4.2. MATERIAL 127
99.3.11.5. SIGN HARDWARE AND POSTS 127
99.3.11.5.1. SIGN HARDWARE 127
99.3.11.3.2. GALVANIZED CHANNEL POSTS 128
99.3.11.6. STANCHIONS 128
99.3.11.7. STEEL GUIDE RAIL 128
99.3.11.7.1. GENERAL 128
99.3.11.7.2. GUIDE RAIL TYPES 128
99.3.11.7.3. GUIDE RAIL TERMINALS 128
99.3.11.7.4. SPECIAL AUGURING 129

99.3.11.8. REINFORCED CONCRETE BUMPER GUARDS 129
99.3.11.9. STREET LIGHTING 129
99.3.12. FIRE HYDRANTS.....130
99.4.1. CONSTRUCTION AND DESIGN STANDARDS 137
99.4.1. STREETS.....138
99.4.1.1. STREET Classifications.....138
99.4.1.2. STREET Grading and Paving Standards.....138
99.4.1.2.1. Principal Arterial and Minor Arterial 138
99.4.1.2.2. Collector 138
99.4.1.2.3. Local Industrial and Local Commercial 138
99.4.1.2.4. Local Residential 139
99.4.1.2.5. Trench Repaving in Bituminous Paving 139
99.4.1.2.6. Special Underdrains 139
99.4.1.2.7. Two Phase Paving 139
99.4.1.2.8. Curb Ramps.....140
99.4.1.3. STREET Design Criteria.....140
99.4.1.3.1. All STREET Classifications except Local Residential 140
99.4.1.3.2. Local Residential STREET 140
99.4.1.3.3. Local Residential and Commercial Cul-de-Sac 142
99.4.2. STORMWATER MANAGEMENT FACILITIES.....143
99.4.2.1. STORM SEWER PIPE 143
99.4.2.2. Storm Inlets 143
99.4.2.3. Storm Manholes 143

99.4.2.4. Post-Construction Stormwater Best Management Practices 143
99.4.2.5. Storm Sewer Lateral Connection 145
99.4.2.6. Stormwater Detention Facilities 145
99.4.2.6.1. Design Storms 145
99.4.2.6.2. Calculation Methods 146
99.4.2.6.3. Underground Infiltration 146
99.4.2.6.4. Dry Detention Impoundments 146
99.4.2.6.5. Wet Pond Impoundments 147
99.4.2.6.6. Underground Detention Facilities 147
99.4.2.6.7. Storm Water Detention Facility Maintenance 147
99.4.2.6.8. As-Built Drawings 147
99.4.2.7. Cradles and Reinforcements for Sewers 147
99.4.2.8. Endwall Details 148
99.4.2.9. Concrete Encasement and Anchors for Sewers 148
99.4.2.10. Connection for Drop Manholes 148
99.4.2.11. Design Criteria for Stormwater Collection/Conveyance Facilities 148
99.4.3. SANITARY SEWER SYSTEM 148
99.4.3.1. Sanitary Sewer Pipe 148
99.4.3.2. Sanitary Manholes 148
99.4.3.3. Sanitary Sewer Lateral Connections 148
99.4.3.4. Cradles and Reinforcements for Sewers 149
99.4.3.5. Concrete Encasement and Anchors for Sewers 149
99.4.3.6. Connections for Drop Manholes 149

99.4.4. PEDESTRIAN CIRCULATION 149
99.4.4.1. SIDEWALKS (concrete).....149
99.4.4.2. WALKWAYS (bituminous).....149
99.4.5. DRIVEWAYS – Access onto TOWNSHIP STREETS 149
99.4.5.1. General Requirements 149
99.4.5.2. General Location Restrictions 150
99.4.5.3. Specific Location Restrictions.....150
99.4.5.4. Number of DRIVEWAYS.....150
99.4.5.5. Approaches to DRIVEWAYS.....151
99.4.5.6. DRIVEWAY Classification 151
99.4.5.7. General DRIVEWAY Design 152
99.4.5.8. Angle of Access DRIVEWAY Approach 152
99.4.5.9. DRIVEWAYS Adjacent to Intersections 152
99.4.5.10. Multiple DRIVEWAYS 153
99.4.5.11. Clear Sight Triangle 153
99.4.5.12 Sight Distance.....153
TABLE 4.5.12.1. 154
99.4.5.13. Grade of Access DRIVEWAY.....155
99.4.5.14. Access DRIVEWAY Pavement 156
99.4.5.15. Curbing Requirements.....156
99.4.5.16. Auxiliary Lanes, Median Openings, Shoulder Upgrading and Traffic Control Devices.....156
99.4.6. PARKING AREAS AND DRIVEWAYS ON LOTS.....156
99.4.6.1. Minimum Paving Standards 156

99.4.6.2. Parking Area Standards 157

99.4.6.2.1. Slopes 157

99.4.6.2.2. Curbs 158

99.4.6.3. DRIVEWAY Standards 158

99.4.6.3.1. Grade 158

99.4.6.3.2. Width of DRIVEWAYS other than Parking Aisles and other than Single Family 158

99.4.7. FIRE HYDRANTS 159

99.4.7.1. Public Water Main Pipe Sizing 159

99.4.7.2. Spacing Between Public Fire Hydrants 159

99.4.7.2.1. Maximum Spacing Between Public Fire Hydrants 159

99.4.7.2.2. Exception 159

99.4.7.3. Spacing Between Private Fire Hydrants 159

99.4.7.4. Fire Hydrant Specifications 160

99.4.8. GUIDE RAILS 161

99.4.9. CABLE TV 162

99.4.10. ELECTRIC 162

99.4.11. GAS 162

99.4.12. WATER 162

99.4.13. MONUMENTS AND MARKERS 162

99.4.13.1. Location 162

99.4.13.2. Type, Material and Size 162

99.4.14. STREET NAME SIGNS 163

99.4.15. STREET LIGHTING 163

99.4.16. SITE LIGHTING 164

99.5. ILLUSTRATIONS 167

99.6. BID DOCUMENTS AND FORMS A-1

99.6.1. NOTICE TO BIDDERS A-2

99.6.1. NOTICE TO BIDDERS A-2

99.6.1.1. PROJECT Description A-2

99.6.1.2. Time and Place of BID Opening A-2

99.6.1.3. Location and Cost of Documents A-2

99.6.1.4. Bonding Requirements A-2

99.6.1.5. BID BOND A-3

99.6.1.6. Non-Collusion Affidavits A-3

99.6.1.7. Delivery of BIDS A-3

99.6.1.8. Term of BID A-3

99.6.1.9. Term of Informalities A-3

99.6.1.10. Dates of Publication A-3

99.6.1.11. Pre-Qualifications A-3

99.6.2. FORM OF SCOPE OF WORK AND PROJECT SPECIFICATIONS AND ADDENDUM FORM A-4

99.6.2. SCOPE OF WORK AND PROJECT SPECIFICATIONS A-4

99.6.2.1. PROJECT SPECIFICATIONS A-4

99.6.2.2. SPECIAL CONDITIONS A-4

99.6.2.3. CONSTRUCTION DETAILS A-5

99.6.2.4. MATERIALS A-5

99.6.2.5. BASIS OF PAYMENT A-5
99.6.3. FORM OF BID A-8
99.6.3. BID A-8
99.6.3.1. Address A-8
99.6.3.2. PROJECT Description A-8
99.6.3.3. Response to Invitation A-8
99.6.3.4. Time of Completion A-8
99.6.3.5. Bidding Schedule A-9
99.6.3.6. BID SURETY A-9
99.6.3.7. To Execute CONTRACT A-9
99.6.3.8. Acceptance of Terms A-9
99.6.3.9. Furnish CONTRACT BONDS A-9
99.6.3.10. Examined Site, Etc. A-9
99.6.3.11. Non-Collusion Affidavit A-9
99.6.3.12. Insurance to be Furnished A-10
99.6.3.13. BID BOND Conditions A-10
99.6.3.14. Signature A-10
99.6.4. FORM OF NON-COLLUSION AFFIDAVIT/INSTRUCTIONS A-12
99.6.4. INSTRUCTIONS FOR NON-COLLUSION AFFIDAVIT A-12
99.6.5. FORM OF INSTRUCTIONS TO BIDDERS A-16
99.6.5. INSTRUCTIONS TO BIDDERS A-16
99.6.5.1. General A-16

99.6.5.2. Definition of Terms A-16

99.6.5.3. Copies of Bidding Documents A-20

99.6.5.4. Examination of CONTRACT DOCUMENTS and Site A-20

99.6.5.5. Interpretations of or Addenda to CONTRACT DOCUMENTS A-21

99.6.5.6. BID Security A-22

99.6.5.7. Date of Starting and Completion A-22

99.6.5.8. Liquidated Damages A-23

99.6.5.9. Notice Prior to Start of WORK A-23

99.6.5.10. Substitute Materials and Equipment A-23

99.6.5.11. SUBCONTRACTORS A-24

99.6.5.12. BID Form A-25

99.6.5.13. Submission of BID A-25

99.6.5.14. Withdrawal of BIDS A-25

99.6.5.15. Receiving and Opening of BIDS A-25

99.6.5.16. BIDS to Remain Open A-25

99.6.5.17. Supplemental UNIT PRICES A-26

99.6.5.18. Lump Sum CONTRACTS A-26

99.6.5.19. Award of CONTRACT A-26

99.6.5.20. Rejection of BIDS A-27

99.6.5.21. CONTRACTOR to be Satisfactory (Most Responsible BIDDER) A-27

99.6.5.22. Performance and Other BONDS A-27

99.6.5.23. Signing of the AGREEMENT A-28

99.6.5.24. Minimum Wage Rates A-28

99.6.5.25. FINANCIAL SECURITY A-28
99.6.5.26. Pennsylvania Human Relations Act A-29
99.6.5.27. Insurance A-30
99.6.5.28. Fictitious Name Registration A-32
99.6.5.29. Non-Collusion Affidavit A-32
99.6.5.30. Prevailing Wage A-32
99.6.5.31. Steel Products A-32
99.6.6. FORM OF NOTICE OF AWARD A-33
99.6.6. NOTICE OF AWARD A-33
99.6.7. FORM OF CONTRACT A-35
99.6.7. AGREEMENT A-35
99.6.7.1. Preamble, Parties and WORK Description A-35
99.6.7.2. Definitions of Terms; CONTRACT DOCUMENTS (Schedule) A-35
99.6.7.3. ENGINEER A-36
99.6.7.4. CONTRACT TIME A-36
99.6.7.5. CONTRACT PRICE; CONTRACTOR'S Warranties and Acceptance A-36
99.6.7.6. Notice Prior to Start of WORK A-37
99.6.7.7. PUBLIC IMPROVEMENTS CODE A-37
99.6.7.8. Payment Procedure A-38
99.6.7.9. CONTRACTOR'S Representations A-39
99.6.7.10. CONTRACTOR'S Employees A-39
99.6.7.11. No-Lien AGREEMENT A-40
99.6.7.12. CHANGE ORDERS; Extra WORK A-40

99.6.7.13. BONDS and Insurance A-41
99.6.7.14. Non-Assignability A-41
99.6.7.15. Final Payment A-41
99.6.7.16. Miscellaneous A-42
99.6.7.17. Execution Form A-42
99.6.8. FORM OF PERFORMANCE BOND A-44
99.6.8. PERFORMANCE BOND A-44
99.6.9. FORM OF LABOR AND MATERIAL PAYMENT BOND A-48
99.6.9. LABOR AND MATERIAL PAYMENT BOND A-48
99.6.10. FORM OF CERTIFICATE OF PUBLIC LIABILITY A-51
99.6.10. CERTIFICATE OF PUBLIC LIABILITY INSURANCE A-51
99.6.11. FORM OF NOTICE TO PROCEED A-53
99.6.11. NOTICE TO PROCEED A-53
99.6.12. FORM OF NOTICE OF COMMENCEMENT A-55
99.6.12. NOTICE OF COMMENCEMENT A-55
99.6.13. FORM OF CHANGE ORDER A-56
99.6.13. CHANGE ORDER NO. A-56
99.6.14. FORM OF GENERAL CONDITIONS A-58
99.6.14.1. Definitions A-58
99.6.14.2. Preliminary Matters A-58
99.6.14.3. Correlation, Interpretation and Intent of CONTRACT DOCUMENTS A-61
99.6.14.4. Availability of Lands; Physical Conditions; Reference Points A-62
99.6.14.5. BONDS and Insurance A-63

99.6.14.6. CONTRACTOR'S Responsibilities A-64

99.6.14.7. WORK by Others A-75

99.6.14.8. TOWNSHIP'S Responsibilities A-76

99.6.14.9. ENGINEER'S Status During Construction A-76

99.6.14.10. Change of CONTRACT PRICE A-78

99.6.14.11. Change of the CONTRACT TIME A-80

99.6.14.12. Warranty and Guarantee; Tests and Inspections; correction, Removal or Acceptance of Defective WORK A-80

99.6.14.13. Payments and Completion A-84

99.6.14.15. Suspension of WORK and TERMINATION A-92

99.6.14.16. MISCELLANEOUS A-94

99.6.15. SUPPLEMENTARY CONDITIONS A-98

99.6.15. SUPPLEMENTARY CONDITIONS A-98

99.6.15.1. General A-98

99.6.15.2. Definitions A-98

99.6.15.3. Other Clarifications A-99

99.6.15.4. Dispute Resolution A-100

99.6.16. ACCEPTABLE FORMS OF SECURITY A-108

99.6.16.1 Form of Irrevocable Letter of Credit – Performance A-108

99.6.16.2. Form of Irrevocable Letter of Credit – Maintenance A-110

99.6.16.3. Performance Bond (Public Or Private Improvements from Developer to Township) A-112

99.6.16.4. Performance Bond (Grading Permits) A-115

99.6.16.5. Performance Bond/Dual Obligee (Where Developer Is Not Providing Bond; Contractor For Developer is Providing Bond) A-118

99.6.16.6. Maintenance Bond..... A-122

99.6.16.7 Escrow Agreement A-125